

BILANS ROBÓT ZIEMNYCH – Żurawia

Pikietta	Pow. wykopu [m ²]	Pow. nasypu [m ²]	Odległość [m]	Obj. wykopu [m ³]	Obj. nasypu [m ³]	Catkowita obj. wykopu [m ³]	Catkowita obj. nasypu [m ³]	Obj. netto [m ³]
0+001.0	0.2	1.8	0.00	0.0	0.0	0.0	0.0	0.0
0+011.5	0.3	3.4	10.44	2.7	27.3	2.7	27.3	-24.5
0+039.0	0.6	3.3	27.53	12.7	92.3	15.4	119.6	-104.2
0+062.6	0.3	4.3	23.63	10.4	89.9	25.8	209.5	-183.7
0+095.0	0.4	3.4	32.40	11.8	125.8	37.6	335.2	-297.6
0+113.1	0.5	3.3	18.09	8.2	60.6	45.8	395.8	-350.0
0+147.1	0.3	3.6	33.96	13.0	116.4	58.8	512.2	-453.5
0+179.7	0.6	2.7	32.65	14.6	102.4	73.3	614.6	-541.3
0+207.8	0.4	3.6	28.04	13.7	89.0	87.0	703.6	-616.5
0+230.1	0.1	6.1	22.34	5.1	108.6	92.1	812.2	-720.1
0+254.0	0.1	6.5	23.89	1.4	149.5	93.5	961.7	-868.2
0+265.1	0.1	5.9	11.10	1.0	69.0	94.5	1030.7	-936.2
0+273.7	0.3	5.9	8.59	1.5	51.0	96.0	1081.7	-985.7
0+285.3	0.3	5.6	11.59	3.1	66.7	99.1	1148.5	-1049.4
0+304.9	0.4	4.7	19.62	6.7	100.6	105.8	1249.1	-1143.2
0+331.8	0.2	6.0	26.95	8.2	144.6	114.1	1393.7	-1279.6
0+352.4	0.1	6.0	20.57	3.5	124.2	117.6	1517.8	-1400.3
0+359.8	0.1	4.9	7.40	0.7	41.7	118.3	1559.5	-1441.2

Tab. 3. Objętość robót ziemnych ul. Żurawia